ADOPTED DECEMBER 17, 2013

BATH ROAD MASTER PLAN

prepared for: **Town of Wiscasset**

prepared by:

T·Y·LIN INTERNATIONAL

in association with:

MRLD Landscape Architecture + Urbanism
Kevin Hooper Associates
Planning Decisions

Plan was developed through funding provided by the Maine Department of Transportation and the Town of Wiscasset

Bath Road Master Plan

Wiscasset, Maine

Prepared for:

Town of Wiscasset

Report funded by MaineDOT and the Town of Wiscasset

Adopted December 17, 2013

Prepared by:

T.Y. Lin International
MRLD
Kevin Hooper Associates
Planning Decisions

TABLE OF CONTENTS

Executive Summary **1**
Master Plan Recommendations **3**
1. Transportation 4
2. Zoning 6
3. Design Standards 9
4. Finance 10
1.0 INTRODUCTION **12**
2.0 EXISTING CONDITIONS **13**
2.1 Transportation Data **13**
2.1.1 Existing Average Annual Daily Traffic Volumes 13
2.1.2 Hourly Traffic Volume Variation 13
2.1.3 Monthly Traffic Volume Variation 15
2.1.4 Weekday Traffic Volume Variation 16
2.1.5 Intersection Turning Movement Volumes 17
2.1.6 Vehicle Classification 18
2.1.7 Pedestrian Volumes 20
2.1.8 Bicycle Volumes 20
2.1.9 Speed Study 20
2.1.10 Crash History 22
2.1.11 Existing Level of Service 22
2.1.12 Transportation Infrastructure Inventory 26
2.1.13 MaineDOT Highway Priority and Customer Service Levels 33
2.2 Planning Data **37**
2.2.1 Zoning, Comprehensive Plan and the Land Use Ordinance Analysis 37
2.2.2 Character Areas 40
2.2.3 Visual Inventory 46
2.2.4 Environmental Constraints 54
2.2.5 Infrastructure 55
3.0 FUTURE TRANSPORTATION CONDITIONS **58**
3.1 Future Traffic Volume Forecast Methodology **58**
3.2 Historical Building Permits **58**
3.3 Future Intersection Turning Movement Volumes (2030) **60**
3.4 Future (2030) Level of Service **61**
4.0 PUBLIC OUTREACH **65**
4.1 Steering Committee Meetings **65**
4.2 Mission Statement - Project Goals **66**
4.3 Business/Property Owner Meetings **66**
4.4 Public Meetings **66**
5.0 RECOMMENDATIONS **67**
5.1 Transportation Recommendations **67**
5.1.1 Intersection Recommendations 68
5.1.2 Bath Road Corridor Recommendations 72
5.1.3 Street Network Connectivity 74
5.1.4 Access Management 76
5.1.5 Cost Estimate and Implementation of Proposed Highway Improvements 79
5.1.6 MaineDOT Route 1 Road Safety Audit 83

5.2 Land Use Recommendations..... 88
5.2.1 Bath Road Vision Overview 88
5.2.2 Proposed Bath Road Mixed-Use District..... 90
5.2.3 Proposed Bath Road Commercial District..... 100
5.2.4 Proposed Bath Road Village 3 District..... 105
5.2.5 Proposed Bath Road Zoning 112
5.3 Potential Funding Strategy 116
5.3.1 Bath Road Corridor Transportation Improvements 116
5.3.2 Financial Responsibility 116
5.3.3 Potential Funding Strategies 119

Appendices

Appendix A **Existing Access Management Figures**
Appendix B **Corridor Improvement Figures**
Appendix C **Access Management Standards and MaineDOT Permits**
Appendix D **Meeting Notes**
Appendix E **Traffic Analysis**

LIST OF FIGURES

Figure ES-1 Study Area 2
Figure ES-2 Proposed Zoning Districts 7
Figure 2-1 Existing Average Annual Daily Traffic Volumes 14
Figure 2-2 2011 Existing Hourly Traffic Volumes 15
Figure 2-3 2011 Existing Monthly Traffic Volumes 15
Figure 2-4 2011 Total Weekday Traffic Volumes 16
Figure 2-5 2011 Northbound Weekday Traffic Volumes 16
Figure 2-6 2011 Southbound Weekday Traffic Volumes 17
Figure 2-7 2012 Intersection Turning Movement Volumes 19
Figure 2-8 Average AM and PM Vehicle Speeds 21
Figure 2-9 2009-2011 Intersection Crash History 23
Figure 2-10 2009-2011 Roadway Segment Crash History 24
Figure 2-11 Existing Regulatory Signage 27
Figure 2-12 MaineDOT Customer Service Levels 34
Figure 2-13 MaineDOT Customer Service Safety Levels 35
Figure 2-14 MaineDOT Customer Service Condition Levels 36
Figure 2-15 Existing Zoning 38
Figure 2-16 View south of transitional Village 2 District 39
Figure 2-17 Character Areas 42
Figure 2-18 The Miss Wiscasset Diner / Wiscasset Trading Post –authentic roadside 43
Figure 2-19 North of the Border –authentic roadside 43
Figure 2-20 Huber's Market – authentic roadside 43
Figure 2-21 Maine Heritage Village – thematic roadside versus authentic roadside 44
Figure 2-22 Shell / McDonald's / Lil' Mart / First Federal Savings – New Development 44
Figure 2-23 New Development site cleared for development 44
Figure 2-24 Strip Development – expansive and cluttered views 45
Figure 2-25 Residential Development on Page Avenue –West of Traditional Development 45
Figure 2-26 View north entering the Village 2 District transitional zone 46
Figure 2-27 Objects and Edges 48
Figure 2-28 Sight Lines and Focal Points 49
Figure 2-29 View north on Route 1 in Woolwich where Maine DOT purchased 50
frontage development rights 50
Figure 2-30 A redeveloped site. 50
Figure 2-31 A well maintained, but highly visible gas station 50
Figure 2-32 A simple, legible, and well-proportioned sign 50
Figure 2-33 The inventory is the sign. 51
Figure 2-34 Forested or undeveloped edge 51
Figure 2-35 Developed edge 51
Figure 2-36 The visual impact of the utility 52
Figure 2-37 Above ground utility lines are less visible 52
Figure 2-38 A field with a development that minimizes the visual impact 52
Figure 2-39 A sight line north from the intersection with Old Bath Road 53
Figure 2-40 A sight line north Montsweag Brook 54
Figure 2-41 The view of Montsweag Brook when standing on the bridge 54
Figure 2-42 Environmental Constraints 56
Figure 2-43 Infrastructure 57
Figure 3-1 2030 PM Peak Intersection Turning Movement Volumes 62
Figure 5-1 Potential Future Street Northern Connections 70

Figure 5-2 Potential Future Street Southern Connections....70
Figure 5-3 Topsham, ME Connector Road Example....75
Figure 5-4 Example of Inter Parcel Connection, Route 1, Falmouth, ME....76
Figure 5-5 Proposed Zoning....90
Figure 5-6 Route 144/Bath Road Proposed Intersection Improvements....93
Figure 5-7 Illustrative Connectivity Master Plan....94
Figure 5-8 Illustrative Connectivity Master Plan with Phasing....95
Figure 5-9 Conceptual Ideal Site Map....96
Figure 5-10 Bath Road Development with Inter-Parcel Connectivity....98
Figure 5-11 Concept Retrofitted Center Lane....99
Figure 5-12 Bath Road Commercial District with Commercial Improvements....103
Figure 5-13 Cross-section through Bath Road....110
Figure 5-14 Bath Road Village 3 District with Corridor Improvements....111

LIST OF TABLES

Table ES-1 Proposed Highway Improvements, Estimated Costs, Timelines and Fund Sources. 4
Table ES-2 Zoning and Land Use Policy Recommendations 8
Table 2-1 Intersection Count Information..... 17
Table 2-2 Intersection Peak Hours 18
Table 2-3 Existing Peak Hour Traffic Volume Comparison..... 18
Table 2-4 Percent Trucks between 6:00AM – 6:00PM..... 20
Table 2-5 Level of Service Criteria for Intersections..... 25
Table 2-6 Existing PM Peak Hour – Capacity Analysis Bath Rd @ Route 144..... 25
Table 2-7 Existing PM Peak Hour – Capacity Analysis Bath Rd @ Shaw's/Shopping Center Plaza 25
Table 2-8 Existing PM Peak Hour – Capacity Analysis Bath Rd @ Old Bath Rd (S) 26
Table 2-9 Existing PM Peak Hour – Capacity Analysis Bath Rd @ Birch Point Rd 26
Table 2-10 Existing PM Peak Hour – Capacity Analysis Bath Rd @ Old Bath Rd (N) 26
Table 2-11 Regulatory Signage Summary 28
T**able** 3-1 B**uilding** P**ermits** b**etween** 2003 and 2012..... 58
Table 3-2 Existing and Future Traffic Volume Comparison Weekday PM Peak Hour..... 61
Table 3-3 Future (2030) PM Peak Hour – Capacity Analysis Bath Rd @ Route 144 63
Table 3-4 Future (2030) PM Peak Hour – Capacity Analysis Bath Rd @ Shaw's/Marketplace Shopping Center Plaza 63
Table 3-5 Future (2030) PM Peak Hour – Capacity Analysis Bath Rd @ Old Bath Rd (S). 63
Table 3-6 Future (2030) PM Peak Hour – Capacity Analysis Bath Rd @ Birch Point Rd... 64
Table 3-7 Future (2030) PM Peak Hour – Capacity Analysis Bath Rd @ Old Bath Rd (N) 64
Table 5-1 Bath Rd @ Route 144 Level of Service Summary with Improvements ..... PM Peak Hour..... 69
Table 5-2 Bath Rd @ Shaw's/Shopping Center Plaza Level of Service Summary (No Improvements Proposed) PM Peak Hour..... 69
Table 5-3 Bath Rd @ Old Bath Rd (S) Level of Service Summary with Improvements PM Peak Hour..... 71
Table 5-4 Bath Rd @ Birch Point Road Level of Service Summary with Improvements PM Peak Hour..... 71
Table 5-5 Bath Rd @ Old Bath Rd (N) Level of Service Summary (No Improvements Proposed) PM Peak Hour..... 72
Table 5-6 Wiscasset Road Safety Audit 2012 - All Potential Strategies Identified……...83
Table 5-7 Proposed Highway Improvements, Estimated Costs, Timelines and Fund Sources 84
Table 5-8 Proposed Use Table 113